Sl No	App Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
91	29.07	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a minimum of 60- 70	Sqm	4515.48	*Rupees Four Thousand Five Hundred Fifteen And Paise Forty Eight Only*
92	44.1	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a minimum of 60- 70 microns with exterior durable pure polyester grade powder of approved quality (FIRST FLOOR) ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Sqm	4520.88	*Rupees Four Thousand Five Hundred Twenty And Paise Eighty Eight Only*
93	4.95	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a minimum of 60- 70	Sqm	4526.28	*Rupees Four Thousand Five Hundred Twenty Six And Paise Twenty Eight Only*
94	567	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work . (GROUND FLOOR) ---- All terms and condition are as per Tender Document	Kgs	84.24	*Rupees Eighty Four And Paise Twenty Four Only*

Contractor

Executive Engineer,
Project Division.

Executive Engineer
Project Division
Yelahanka Zon
Bangalore

	Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate in Words	Rate in Figures
			4	5	6
	2	3			
	812.7	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and condition are as per Tender Document	Kgs	89.64	Rupees Eighty Nine And Paise Sixty Four Only
96	94.5	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work . (SECOND FLOOR) ---- All terms and condition are as per Tender Document	Kgs	95.04	Rupees Ninety Five And Paise Four Only
97	60.21	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work . (GROUND FLOOR) ---- All terms and condition are as per Tender Document	Sqm	6638.76	Rupees Six Thousand Six Hundred Thirty Eight And Paise Seventy Six Only
98	41.17	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and condition are as per Tender Document	Sqm	6644.16	Rupees Six Thousand Six Hundred Forty Four And Paise Sixteen Only
99	16.2	Providing and fixing M.S. Gate as per Chief Architect Drawing,using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specifiocation and as per directions of the Engineer in charge of the work. ---- All terms and condition are as per Tender Document	Sqm	3168.72	Rupees Three Thousand One Hundred Sixty Eight And Paise Seventy Two Only
100	164.52	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and condition are as per Tender Document	Sqm	88.56	Rupees Eighty Eight And Paise Fifty Six Only
101	4	Providing 20mm square M.S footrest and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work. ---- All terms and condition are as per Tender Document	Nos	265.68	Rupees Two Hundred Sixty Five And Paise Sixty Eight Only

Contractor

Executive Engineer,
Project Division.

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

p Qty	Description of work	K.GOPIREDDY		
		Unit	Rate in Words	Rate in Figures
2	3	4	5	6
3422.03	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., complete as per the direction of the Engineer-in-charge. ---- All terms and condition are as per Tender Document	Cum	108.0	Rupees One Hundred Eight Only
03 167.29	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., complete as per the direction of the Engineer-in-charge. ---- All terms and condition are as per Tender Document	Cum	80.35	Rupees Eighty And Paise Thirty Five Only
104 50	Supplying 6A flush /projected type socket and a 6 amps flush/projected type SP switch either surface mounting in a gang box or in a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	No	91.0	Rupees Ninety One Only
105 30	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work complete. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Each	98.0	Rupees Ninety Eight Only
106 30	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work complete. b) 12"x12"x3" ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Each	68.0	Rupees Sixty Eight Only
107 200	Extra for groove cutting, plastering and colour washing for embedding PVC conduit/GI pipe and plastering finishing the wall upto wall surface complete upto 50mm conduit in brick in wall c) 10"x7"x3" ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Rmtr	14.0	Rupees Fourteen Only
108 2	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit..... The pit should be filled with equal proportion of salt and charcoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as per IS1 specification 7.3.3 of IS 732 using 12 mm dia bolts, nuts, washers and checknuts etc, the pipe shall have 16 through holes of 122 mm dia ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Each	3000.0	Rupees Three Thousand Only
109 12	Supplying and fixing of porcelain fuse chanel with cut out on existing wooden/panel using ncessary nuts, bolts and washers etc complete ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Each	54.0	Rupees Fifty Four Only
110 200	Supplying 20mm dia 2mm thick heavy guage PVC conduit pipe with suitable size bends, metal junction boxes, adhesive paste etc and running before concreting the slabs. The conduit should be tied to the reinforcement roads by using binding wire and unused ways of junction boxes and pipe ends should be covered using PVC and enclosures and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Rmtr	32.0	Rupees Thirty Two Only
111 50	Supplying and fixing PBBC brass/Bakelite straight or slant batten holder and wiring, within 60W/230 Volts lamps ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	No.	60.0	Rupees Sixty Only
112 30	Supply patty type fluorescent tube light fitting of 4 feet 40 watts fluorescent tube of 230 volts made of M.S. sheet and stove enameled with heavy duty polyfill aluminum choke, starter, locking type brass contact holders mounted on foldable type sheet base fully wired.for use on 230 volts AC supply including 1 Nos 4'-36/40 watts fluorecent tube A Group ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	No	400.0	Rupees Four Hundred Only
113 1000	Wiring for lighting / power circute using one of PVC insulated 1100v/grade multies and copper conductor single core cable in open or consealed system of wiring A Group materials 1.50 Sqmm materials ---- All terms and condition are as per Tender Document	Rmtr	15.0	Rupees Fifteen Only

Contractor

Executive Engineer,
Project Division.

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Competent Authority.

Sl No	App Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate In Words	Rate In Figures
1	2	3	4	5	6
114	48	Supplying and running of GI / Copper conductor for grounding & (along with other wires of CTS or conduit system of wiring) using if necessary suitable size clamps bolts nuts and washers etc. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Rmtr	221.0	Rupees Two Hundred Twenty One Only
115	10	Supplying and fixing miniature circuit breakers/Isolators on existing MCB distribution boards using necessary fixing materials and wiring complete as required ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	No.	370.0	Rupees Three Hundred Seventy Only
116	25	Supplying capacitor type ceiling fan complete with down rod blades, shakle, regulator canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system and as per technical data approved (Almanord, Unique ISI, Anchor, Crompton, Khaitan, Bajaj, Usha, Johnson make) ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Nos	1900.0	Rupees One Thousand Nine Hundred Only
117	25	Fixing a ceiling fan of all capacities and all types to the existing S hook with fan regulator to the existing board together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely ---- All terms and condition are as per Tender Document	Nos	105.0	Rupees One Hundred Five Only
118	200	Digging of trench of 0.6m deep x 0.50mtr wide refiling the trench to the required ground level and consolidating etc., complete. In Hard Soil ---- All terms and condition are as per Tender Document	Rmtr	50.0	Rupees Fifty Only
119	12	Constructing brick masonry inspection chamber 600x850mm, and 450mm depth, (clear inside dimension) for pipeline with three or more inlets, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover with frame (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal , foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finished smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Nos	9522.36	Rupees Nine Thousand Five Hundred Twenty Two And Paise Thirty Six Only
120	38.4	Excavation by manual means for foundation of buildings, water supply & sanitary lines and electrical conduits etc., either in pits or in trenches 1.50m and above in width, soft rock without blasting not exceeding 1.50mts in depth including stacking the excavated stuff clear from edges of excavation with lead upto 50m labour, HOM of equipment complete as per specifications ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Cum	953.64	Rupees Nine Hundred Fifty Three And Paise Sixty Four Only
121	80	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipmentsand testing complete as per specifications. 11.56.2 -do- with 110mm outer dia ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	m	743.04	Rupees Seven Hundred Forty Three And Paise Four Only
122	120	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	m	1566.0	Rupees One Thousand Five Hundred Sixty Six Only
123	100	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure 25mm outside diameter chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	m	117.72	Rupees One Hundred Seventeen And Paise Seventy Two Only

Contractor

Executive Engineer,
Project Division.

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Sl No	App Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
124	14	Providing stoneware gully trap of approved quality and make fixing in M-15 and plastering with CM 1:3 wherever necessary.(Rate includes cost of all materials, fixtures and lead) 10cms x 10cms ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Nos	199.8	Rupees One Hundred Ninety Nine And Paise Eighty Only
125	4000	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer Black or Blue and inner White layer of approved quality and make, conforming to I.S.I./ISO/SSI specifications. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Ltr	6.48	Rupees Six And Paise Forty Eight Only
126	4	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	nos	648.0	Rupees Six Hundred Forty Eight Only
127	4	Providing and fixing in position brass ball valve high or low pressure with plastic float of approved quality 25mm dia nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Each	654.48	Rupees Six Hundred Fifty Four And Paise Forty Eight Only
128	30	Providing and fixing in position brass bib cock of approved quality 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Each	293.76	Rupees Two Hundred Ninety Three And Paise Seventy Six Only
129	18	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, S-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre white glazed vitreous china clay low level, flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials ,labour complete as per specifications ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Each	5351.4	Rupees Five Thousand Three Hundred Fifty One And Paise Forty Only
130	25	Providing and fixing white vitreous china clay, angle back wash basin size 600x480mm with a single 15mm C.P brass pillar tap with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Unit	3383.64	Rupees Three Thousand Three Hundred Eighty Three And Paise Sixty Four Only
131	5	Providing and fixing C.P. brass towel rail 600 mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P. brass screws including cost of materials, labour complete as per specifications, ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	nos	766.8	Rupees Seven Hundred Sixty Six And Paise Eighty Only
132	10	Providing and fixing 1500x450mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Unit	1833.84	Rupees One Thousand Eight Hundred Thirty Three And Paise Eighty Four Only
133	1	Providing and fixing water meter with stop cock, jam nut, socket in G.I pipe line including cutting and threading the pipe and making long screws including cost of all materials, labour, HOM of equipments and testing complete as per specifications. ---- All terms and condition are as per Tender Document and as per the direction of Engineer-in-Charge	Set	1423.44	Rupees One Thousand Four Hundred Twenty Three And Paise Forty Four Only

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

30/11

G.Gopireddy

Contractor

Executive Engineer,
Project Division.